

Item	Description	Qty	Unit	Rate GH¢	Total GH¢
	REHABILITATION OF CHPS COMPOUND AT WORKPOE				
	<u>GLAZING</u>				
A	Pair Louvre Carriers 1200mm long	40	No.		
	150mm wide plain/obscre glass louvre blade with slightly round long exposed edges and into metal clip 900mm long clip	130	No.		
D	50mm x 50mm welded mesh cut into varieuse shapes ,sizes and fixed to window openings	60	m ²		
E	Nylon screen mosquito net fixed on widow openings in varieuse shapes and sizes	60	m ²		
F	20mm diameter pvc conduit including all fixing accessories in floor screeds or chases in block work	300	m		
	Glazing Carried to Summary				-
G	Sanitary Appliances				
	<u>Supply and install the following appliances complete</u>				
H	Approved low level W.C suit complete with trap comprising 9 litres ceramic flushing cistern,push in type twyford	2	No.		
J	White glaze wash hand basin with complete tap	1	No		
K	Industrious Buffer sink complete with tape	1	No		
	Chromuim plated toilet roll holder	2	No.		
L	<u>Plumbing and Engineering works</u>				
	Allow the provisional sum of GHC 6,000.00 for all plumbing pipe work in connection with all pipes and associated fittings and connection to main facility		sum		
	<u>Supply, install and connect the following luminaires with all Necessary accessories complete (lamps,attachments etc.)</u>				
	Carried to SummarySanitary Appliances				-
M	Allow the provisional sum of GHC 40,000.00 for eletrical works		sum		
	Include a provisional sum of GHC 15,000.00 for work in connection with the Nattional Grid and Earthing		sum		
	carried to Summary				-

Item	Description	Qty	Unit	Rate GH¢	Total GH¢
	REHABILITATION OF CHPS COMPOUND AT WORKPOE				
	FLOOR ,WALL AND OTHER FINISHINGS				
	Cement and sand (1:4) as described				
B	12mm backing to receive wall tiles	120	m ²		
C	38mm thick screeding on floor bed to received floor tiles.	220	m ²		
	<u>Ceiling</u>				
D	6mm Plywood fixed to ceiling joists	460	m ²		-
	<u>Tiles</u>				
E	400mm x400mm x 8mm unit to floors on cement and sand base; level to a fall only not exceeding 15 degree from horizontal;plain	180	m ²		-
F	250mm x 500mm x10mm unit to walls on cement and sand based ;plain,with exceeding 300mm	120	m ²		-
	Floor,Wall an finishings carried to Summary:				-
	PAINTING AND DECORATING				
	<u>Prepare surface wall with home charm as base for two finishing coat</u>				
	<u>Prepare and apply two (2) coats of Acrylic emulsion paint to</u>				
H	wall	116	m ²		
	Knot ,stop, prime prepare and apply two(2) undercoat and one (1) finishing coats to				
J	General hardwood surfaces	53	m ²		
K	Soffit of ceiling	300	m ²		
L	Surface not exceeding 300mm girth	60	m		
	Painting and Decoration carried to Summary				

Description	Qty	Unit	Rate GH¢	Total GH¢
<u>JOINNERY/ METAL WORKS</u>				
<u>WINDOWS/DOORS/STAIRS</u>				
<u>L20: TIMBER DOORS/SHUTTERS/HATCHES</u>				
<u>Doors in hardwood; treated with preservative; wrought</u>				
44mm thick (finished) hardwood panel Size 1200mm x 2050mm	4	No.		
Ditto: size 750mm x 2050mm	3	No.		
<u>Door frames in hardwood; treated with preservative; wrought</u>				
50 x 150mm hardwood frame plugged to wall	424	m		
Door stoper	47	m		
Window stoper	36	m		
Butterns	320	m		
<u>WINDOW/DOOR</u>				
Joinnery/Metal Carried to Summary:				
<u>IRONMONGERIES</u>				
<u>Supply and fix the following ironmongeries complete with screws</u>				
1 Pair 150mm brass butt hindges	10	No.		
Mortice lock complete	4	No.		
WC indicator lock complete	3	No.		
Barrel Bolt to doors	8	No.		
Ironmongeries Carried to Summary:				
<u>SUMMARY</u>				
GLAZING				
PLUMBING				
ELECTRICALS				
FINISHING				
PAINTING AND DECORATION				
DOORS AND WINDOW				
IRONMONGERIES				
APPRONE/DRAIN				
SEPTIC TANK				
TOTAL COST OF PROJECT:				-